

**Forming play ground on the Western & Southern sides of the Canteen block in Perumalpattu campus**

**BILL OF QUANTITY**

SNO	QTY	ITEM OF WORK	RATE	PER	AMOUNT
1	180000sft	Clearing the area by hiring JCB,tractor to the entire area and depositing the excess debris in outskirts of campus if required for block level			
		Tentative area Of 180000 sft		Lumpsum	
2	LS	Taking block level of the entire land to assess the average level for forming ground including plotting and submission of drawing		Lumpsum	
3	LS	Levelling the ground to an uniform level by hiring JCB dozer & power roller for improvement the ground to fill GSB		Lumpsum	
4	90000CFT	Supplying granular sub base material including filling spreading by JCB & manual in corners and consolidation by power roller to a smooth thickness of 6" thick including watering & levelling to the required gradient etc as directed by the engineer in charge		cft	
5	60000CFT	Supplying gravel including filling spreading by JCB & manual in corners and consolidation by power roller to a smooth thickness of 4" thick including levelling to the required gradient etc as directed by the engineer in charge etc		cft	
6	330 CFT	Supplying Red earth including filling spreading by JCB & manual in corners and consolidation by power roller to a smooth thickness of 4" thick including levelling to the required gradient etc as directed by the engineer in charge etc (optional)		cft	
7	LS	providing drainage arrangements if required (actuals during work)			
		<b>Total</b>			

**Note:**

- 1 If any GST this may be mentioned
- 2 If any clarification in the schedule this can be cleared under intimation
- 3 If site inspection required it can be done after intimation
- 4 The copy of Pan card should be enclosed along with the tender